


Anatomy of a community-based stream restoration project

Paul Jones, US EPA

in cooperation with the

**San Pedro Valley County Park and the
San Pedro Valley Watershed Coalition**

Project Location



Project Goals

- **Remove a barrier to fish migration**
- **Restore streamside habitat**
- **Demonstrate the effectiveness of the newly formed SPCWC**
 - **an early success**

Description

- Remove a 26' long x 6' diameter concrete culvert
- Lay back the banks, stabilize the site, re-vegetate with native plants, replace crossing with a new bridge



Early Expectations and Constraints

- **Inexpensive**
 - \$20,000 to \$30,000 estimate
 - would use railcar
- **National Fish and Wildlife Grant**
- **Relatively easy to do**
- **Permitting not too complicated**

First Steps

- **Perform physical site inspection, cross sections, and longitudinal profile**
- **Biological assessment**
- **Estimate cost for bridge and materials**

First hints of trouble

- Need free-standing bridge, rated for fire truck access
- Rail cars are expensive, not available, often have lead-based paint
- Engineer needs detailed geotechnical report and site survey
 - expensive, and means another contract
- Bridge costs = total available!!
 - fund raising begins!!@##\$\$%%#!

Design Requirements

- **45-foot long free-standing bridge**
 - fire truck, equestrian, bicycle safe
 - self-maintaining
- **Massive engineering**
 - **Abutments**
 - either 20' wide x 10' high x 8' footer or
 - 6 piers, 2' diameter x 28' depth with massive rebar cages and
 - **Weirs**
 - 8 weirs with 16 quarter-ton boulders per weir

Permits: Oh the joy!

- **Used JARPA**
 - **Some agencies confused process**
 - **County wouldn't go forward without reconciliation**
 - **Some took months to reply, then no comment**
 - **Used Regional General Permit no.1 for 404 permit from Corps of Engineers**
 - **Needed separate 1601 Agreement from DFG**

Permits, continued

- Took over 1 year! @##\$\$%%#
 - Received the 1601 Agreement a few days before construction because DFG was caught in a “Catch 22”
 - There were surprises!
 - County Building Inspector issue

Original Schedule

- JARPA in spring 2000
- Permits in July 2000
- Construction in Sept 2000

Actual Schedule

- JARPA in spring 2000
- Permits July 2001
- Construction July-Nov 2001

Contracting and Construction

- **Urban Creeks Council for survey, design, and construction**
- **JC Engineering for civil engineering**
- **Earth Investigations for geotechnical engineering**
- **Wheeler Bridge Company for the bridge**
- **Brodhead Steel for the rebar cages**
- **Power Engineering for excavator work**

Contracting and Construction, continued

- Collin Tiura and Daughters for drilling and bridge setting
- Go Native for construction, erosion control (donated!!)
- San Mateo County for construction, form building, concrete, site cleanup, debris disposal
- Trucker, pumpers, rock, erosion control materials

OK, Build It!

- **Need more money**
 - sought funds from RWQCB, County Parks Foundation
 - reprogrammed funds in NFWF grant
- **Line up contractors**
 - get estimates
 - sign contracts

OK, Build It! continued

- **Develop detailed construction schedule**
- **Order materials and supplies**
 - signs, fencing, porta potty, nets, pump, hose, flagging, trash can
- **Send checks for bridge, rebar cages, etc.**

Construction Steps

- **Demolition**
- **Drilling**
 - oops, broke an auger and extractor!
 - needed cutting torch for rebar
 - created an attractive nuisance
- **Bank contouring**
- **Erosion control blanketing**

Drilling holes for
piers, installing
casing and rebar
cages



Drill rig and
pumper;
surveying
elevation of
piers and
abutments



Setting casing
before setting
rebar cage and
pouring concrete

NOTE: rebar cage
set high due to
broken auger and
extractor at bottom
of hole



Dropping the 30'
long casing into
drilled holes prior
to pumping
concrete



Constructing
rock weirs;
excavating step
pool



Erosion blanket
installed, piers
stubbed out,
ready to build
abutment forms



Construction Steps, continued

- **Soil bio-engineering**
- **Weir construction**
- **Building the forms for the abutment and pouring concrete**
- **Setting bridge**
- **Site cleanup, grading, planting**

Pumping
concrete
into the
abutment
forms



Lifting
the
bridge
off the
truck




Setting the
bridge on the
abutments





View from the channel of the near-finished product



The first hikers cross the new bridge

Realities

- Personnel issues
- Last minute complications
- SPCWC and the City of Pacifica had joint fiscal responsibilities
 - makes for messy tracking of funding
- Hard to figure out permit requirements
 - inconsistent and not always clear

Monitoring

- quarterly reporting
- troubleshooting
- pounded in the first month
 - 8” rain in 48 hr
 - 22” in December!
 - most rain in that month since 1956

Final Costs

- **Projected: \$30,000**
- **Actual: \$75,000**
- **Actual costs not including in-kind contributions**
 - County
 - SPCWC and EPA
 - Go Native, Power Engineering, and JC Engineering
- **Total probably closer to \$125,000**

Lessons Learned

- Permitting takes a long time
 - *even longer that you think!*
- Costs can skyrocket
 - civil and geo-engineering
 - materials
 - professional services
 - cost overruns (driller, bridge setting)
- “Good planning” is sometimes not good enough
- Be flexible, as things happen
- Add at least 25% to the estimated project cost for contingencies



First storm: so far, so good! This was an 8" storm event